

BILL OF QUNATITY

Name of work: Repair and replacement of drain pipe of FCUs in Chemistry department "P" Block in IITG campus

Sl. No.	Description	Unit	Qty.	Rate in Fig. (Rs.)	Rate in words (Rs.)	Amount (Rs.)
1	Dismantling, cutting, removing of existing GI drain pipe in the in the corridor, including shifting of dismantled pipe to the store area inside new-AC Plant.					
a	50 mm Dia	rm	120			
2	Supply, Laying, fixing, testing and commisioning of following thickness 19 mmclosed cell elastometric nitrile rubber of class "O" applied by self adhesive i/c Chicken wire mesh, 10 mm thick sand cement plaster in two layer i/c painting complete as required.	rm	120			
3	Providing and fixing of CAHU/FCU connection with PVC flexible hose pipe complete as required i/c clamping on both sides.	lot	32			
4	Supply, fabrication and errection of MS support structure suitable for pipe and all necessary accessories like Nuts, Bolts, Support, Anchor fastner, studs, etc.	lot	40			
5	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, i/c cutting and making good the walls etc.					
a	50 mm dia	m	120			
Total amount =						
<u>Discount@.....%, if any =</u>						
<u>Net Quoted amount =</u>						
Say =						

(Rupees.....only)

N.B: Quoted rates shall be inclusive of all taxes & GST