

BOQ

for

Name of Work: Electrical Power Wiring for 50Nos. Insect Killer installed at various locations of Subansiri Hostel in IITG Campus.						
NIT No: IITG/IPM/NIT/FY23-24/62; Dtd-29/02/2024						
Sl. No.	Description of Item	Unit	Qty.	Rate (in Rs.)	Rate in Words	Amount (Rs.)
1.0	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
	a). 2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	Mtr	615			
	b). 2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Mtr	115			
2.0	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
	a). 5/6 A switch	Each	50			
	b).3 pin 5/6 A socket outlet	Each	50			
3.0	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/recess including cutting the wall and making good the same in case of recessed Conduit as required.					
	a). 25 mm	Mtr	450			

4.0	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.					
	a). 3 Module (100mmX75mm)	Each	50			
TOTAL AMOUNT						
Discount@.....%, if any						
GRAND TOTAL AMOUNT						

(Rupees.....)

N.B: Quoted rate should be inclusive of all Taxes.

Date:

Place:

Seal & Signature of Bidder