

Bill of Quantity
for

Replacement of faulty cable of street and Residential feeder pillar in IITG campus

Sl. No.	Description of Item	Unit	Qty.	Rate in Figure (in Rs.)	Rate in Word	Amount (Rs.)
1	Laying of one no PVC insulated and PVC sheathed/ XLPE power cable of 11KV grade of following sizes direct in ground including excavation, sand cushioning , protective covering and refilling the trench etc as required					
	i) Up to 35sqmm	mtr	620			
2	Supply of follwing types and sizes of 1.1KV grade PVC insulated aluminium conductor armored underground cable make havells/RR Kabel/KEI/Finolex					
	i) 4x6 sqmm	mtr	355.00			
3	Supply of 1.1KV grade PVC / XLPE Insulated Armored Aluminium underground cable (Approved Make- Havells,KEI, polycab,RR Kabel,RPG,NICCO,Finolex,CCI, incab)					
	i) 35 sqmm 31/2C	mtr	265			

4	Supply and embedding following GI pipe (medium class) in ground including trenching (75cm deep) and refilling etc as required					
	i) 80 mm dia	mtr	24			
TOTAL AMOUNT						
Discount @.....%, if any						
GRAND TOTAL						

Seal

Date :

Signature of the Tenderer