

BILL OF QUANTITY

Name of work: Repainting of 46 nos room at ground floor of Barak Hostel in IITG Campus.

Item No.	Description of item	Unit	Qty	Rate in figure (₹)	Rate in Words	Amount (₹)
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	Sqm	2302.30			
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm	275.00			
3	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface :	Sqm	275.00			
4	Distempering with 1st quality acrylic distemper, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour. Two or more coats	Sqm	2302.30			
5	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	Sqm	970.00			
	Total Amount ₹ =					
	Rebate if Any =					
	Total Amount after Rebate ₹ =					
	Rounded off =					

(RupeesOnly)